


BRUHATH BENGALURU MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of Executive Engineer

SCHEDULE -B

Name Of Work: Improvements of CC road prashantha Nagara 3rd Cross & pipeline road to Model colony
Main road in Dasarahalli Ward No 15

Sl. No	Description of Work	Unit	Qty	Sanctioned Rate	
				In Figures (Rs.)	In Wards (Rs.)
1	Dismantling of existing structures like culverts, Bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts complete as per specification Lime/Cement concrete I. By Manual Means C. ~~Pre-stressed Reinforced cement concrete Grade M.~~	Cum	211.95	1684.00	
2	Excavation for road, drains and similar works - KSRRB 300-1. Earthwork excavation by manual means in Ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled ~~neatly after breaking of clods complete as per~~	Cum	105.98	137.00	
3	Providing, laying, spreading and compacting graded stone aggregates to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base / base course on well	Cum	162.50	2001.00	
4	Providing and laying Plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @ 0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centering ~~complete as per specifications.~~	Cum	70.65	5000.00	
5	Cement concrete pavement. Construction of unreinforced plain cement concrete pavement, thickness as per design, over a prepared sub base with OPC cement or any other type as per clause 1051.2.2 with 25mm and down size graded granite metal coarse aggregates and fine aggregates, with ~~superplasticiser @ 2% confirming to IS9103, 1999~~	Cum	105.98	5200.00	
6	Vacuum de-watering with vacuum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator, HOM of machinery, screed vibratory, power Floater, blade and disc etc., with all lead and lift	Sqm	706.50	72.00	
7	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add	Cum	105.98	69.00	


Signature of Contractor


Executive Engineer
Dasarahalli Division